

METAL SOLUTIONS

EOS NickelAlloy HX

Material Data Sheet

EOS NICKELALLOY HX

EOS NickelAlloy HX is a nickel-chromium-iron-molybdenum alloy in fine powder form. Its composition corresponds to UNS N06002.

While the wrought and cast versions of the alloy generally are solution annealed, the laser sintered version has a high strength and good elongation already in the as-built condition. Solution annealing of the laser sintered material will homogenize the microstructure, relax internal stresses and increase the elongation, while slightly decreasing the strength. This type of alloy is characterized by having high strength and oxidation resistance also at elevated temperatures, and is often used up to 1200°C. Therefore its applications can be found in aerospace technology, gas turbine parts, etc. Parts built from EOS NickelAlloy HX can be heat treated and material properties can be varied within specified range. In both as-built and solution heat treated states the parts can be machined, spark-eroded, welded, micro shot-peened, polished, and coated if required. Unexposed powder can be reused.

MAIN CHARACTERISTICS

High strength and oxidation resistance also at elevated temperatures up to 1200°C

TYPICAL APPLICATIONS

- Aerospace
- Gas turbine parts


The EOS Quality Triangle

EOS uses an approach that is unique in the AM industry, taking each of the three central technical elements of the production process into account: the system, the material and the process. The data resulting from each combination is assigned a Technology Readiness Level (TRL) which makes the expected performance and production capability of the solution transparent.

EOS incorporates these TRLs into the following two categories:

- Premium products (TRL 7-9): offer highly validated data, proven capability and reproducible part properties.
- Core products (TRL 3 and 5): enable early customer access to newest technology still under development and are therefore less mature with less data.

All of the data stated in this material data sheet is produced according to EOS Quality Management System and international standards



POWDER PROPERTIES

EOS NickelAlloy HX corresponds to UNS N06002.


Powder Chemical Composition (wt.-%)

Element	Min.	Max.
Ni		Balance
Cr	20.5	23
Fe	17	20
Mo	8	10
W	0.2	1
Co	0.5	2.4
C	-	0.1
Si	-	1
Mn	-	1
S	-	0.03
P	-	0.04
B	-	0.01
Se	-	0.005
Cu	-	0.5
Al	-	0.5
Ti	-	0.15

Powder Particle Size

GENERIC PARTICLE SIZE DISTRIBUTION

15 - 65 μm



HEAT TREATMENT

Description

Heat treatment procedure according to AMS2773 and AMS5390

Steps

Solution anneal at 1177°C for 1 hour, followed by rapid air cooling to below 60°C

HEADQUARTERS

EOS GmbH
Electro Optical Systems

Robert-Stirling-Ring 1
82152 Krailling / Munich
Germany

Tel.: +49 89 893 36-0
Email: info@eos.info
URL: www.eos.info

This powder has not been developed, tested or certified as a medical device according to Directive 93/42/EEC (MDD) or Regulation (EU) 2017/745 (MDR) and is not intended to be used as a medical device, in particular for the purposes specified in Art. 2 No. 1 MDR. Insofar as you intend to use the powder as raw material for the manufacture of pharmaceutical products or medical devices (e.g. as raw material which as a material must meet the requirements of Annex 1, Chapter II MDR), the responsibility and liability for all analyses, tests, evaluations, procedures, risk assessments, conformity assessments, approval and certification procedures as well as for all other official and regulatory measures required for this purpose shall lie solely with you both with regard to the pharmaceutical product and/or medical device manufactured by you and with regard to the properties, suitability, testing, evaluation, risk assessment, other requirements for use of the powder as raw material. In this respect, the limitations of liability pursuant to our General Terms and Conditions and the system sales or material contracts shall apply.

Part properties are provided for information purposes only and EOS makes no representation or warranty, and disclaims any liability, with respect to actual part properties achieved. Part properties are dependent on a variety of influencing factors and therefore, actual part properties achieved by the user may deviate from the information stated herein. This document does not on its own represent a sufficient basis for any part design, neither does it provide any agreement or guarantee about the specific properties of a material or part or the suitability of a material or a part for a specific application.

The achievement of certain part properties as well as the assessment of the suitability of this material for a specific purpose is the sole responsibility of the user. Any information given herein is subject to change without notice.

Status as of 26.07.2024. Subject to technical modifications. EOS is certified according to ISO 9001.

EOS®, Additive Minds® Alumide®, AMQ®, CarbonMide®, DirectMetal®, DMLS®, EOSAME®, EOSINT®, EOSIZE®, EOSPACE®, EOSPRINT®, EOSTATE®, EOSTYLE®, FORMIGA®, LaserProFusion®, PA 2200®, PrimeCast® and PrimePart® are registered trademarks of EOS GmbH Electro Optical Systems in some countries. For more information visit www.eos.info/trademarks.